

Assessing Canada's Global Engagement Gap

Second Edition - January, 2017



Global Canada is a non-partisan, non-governmental organization that seeks to advance Canada's global engagement.

The world is looking to Canada. There was massive applause when Prime Minister Justin Trudeau proclaimed at the United Nations this year: **"We're Canadian. And we're here to help."**¹

But is Canada prepared to commit the resources to provide this much needed help? The second edition of *Assessing Canada's Global Engagement Gap*, examines this question in two ways: first, a review of the share of national income committed to collective security and international assistance; second, a deeper dive into Canada's international assistance.

The review of national income committed to collective security and international assistance comes to the same sobering conclusion as last year:

1. Canada is worse than a laggard—it is last among its global peers. Just as we concluded a year ago, using 2014 data, Canada tied for last place with Japan in 2015 ([exhibit 1](#)).
2. Canada, with Japan, is the only country in its peer group failing to reach even halfway to international benchmarks for either collective security or international assistance ([exhibit 2](#)).

The international assistance deep dive concludes that:

3. Canada's commitment to international assistance is near an all-time low ([exhibit 3](#)). Canada is not back—it is far back compared to any reasonable international or historical comparison ([exhibit 7](#)). If the Trudeau government remains on its present course, it will have the lowest commitment to international assistance of any Canadian government in the last half-century ([exhibit 5](#)).
4. This resource gap has a massive human cost. We calculated the lives saved if the missing resources were invested in proven health initiatives. The human cost in 2016 was half a million lives compared to Canada's historical levels of support. The total human cost of Canada's commitment gap since 1995, across Liberal and Conservative governments, is the equivalent of over 7 million lives ([exhibit 8](#)).
5. The strategic rationale for international assistance has seldom been stronger. The world today is at a crossroads between a positive path of increased prosperity and security or a downward spiral into misery, instability, and potentially cataclysmic system collapse. Canada could play a key role.
6. International assistance represents a mere 2% of the federal budget. Budget 2017 can be the moment when the Trudeau government puts Canada, after two decades of free-riding, back on a path to being a fully paid-up member of the international community. Then Canada will truly be back.



1. Canada last on defence plus development

For the second year, we examined Canada's share of national income committed to defence and development. We compared Canada with its closest international peer group: the G7 and a set of mid-sized, advanced, open economies (Australia, Netherlands, Switzerland, Sweden, and Norway) often referred to as "like-minded" countries.

Collective security and international assistance are two of the most important measures of a country's commitment to international peace and development. The OECD measure of international assistance, Official Development Assistance (ODA), is particularly useful as it includes most actions by a government to support developing countries and vulnerable populations: from humanitarian aid, development support, and environmental assistance to refugee resettlement and supporting international students in Canada.

When we first performed this analysis a year ago, using 2014 data with 2014 data, Canada ranked a disappointing last—tied with Japan, a country with constitutional constraints on defence expenditures and two decades of economic malaise. This year, using 2015 data, Canada arrived last again. Canada's global engagement in 2015 as a share of Gross Domestic Product (GDP) was a full 40 percent below its peers ([exhibit 1](#)).

2. Canada less than halfway to international benchmarks for collective security and international assistance

Countries focus their engagement differently: the US and Australia emphasize collective security; Norway and Germany put a stronger focus on international assistance; the UK commits through national legislation to meet international benchmarks for both collective security (2 percent of GDP) and international assistance (0.7 percent of Gross National Income, or GNI).²

Canada and Japan are the only countries that fail to get halfway to either benchmark ([exhibit 2](#)). Canada's 0.97 percent of GDP on collective security is less than half the 2 percent NATO benchmark. Even more striking for a former leader in development, Canada's international assistance of 0.28 percent of GNI is barely a third of the 0.7 percent benchmark adopted by the United Nations—a benchmark met in full by the UK, Netherlands, Sweden and Norway.

At a time of national self-congratulation on our role in the world, it is worth pausing for a moment on these conclusions: Canada is last in its peer group, it contributes a full 40 percent less than average, and it is not even half way to international benchmarks for either collective security or international assistance.

3. On international assistance, Canada is not back—it is way back

Quality and innovation are critical aspects of international assistance. However, quantity is also key.

At a time of unparalleled need with regions in turmoil and more displaced people since the end of WWII, Canada's international assistance as a share of national income is close to an all-time low ([exhibit 3](#)).

How can this be? The inconvenient truth of Canada's fiscal turnaround is that the cost of cuts was borne disproportionately by the most vulnerable of the planet. Cuts to international assistance, as a share of national income, were more than three times deeper than cuts to domestic programs ([exhibit 4](#)).

Twice in 20 years, Canada's books were balanced on the backs of the poorest in the world. The first set of deep cuts took place in the mid 1990s. This was followed by a slow recuperation of less than half the cuts from 2002 to 2010, thanks to commitments made by prime minister Jean Chrétien at the Monterrey Conference on Financing for Development.

Then, from 2010 to 2014 there was a second round of deep cuts. Whereas the first round occurred in a time of fiscal and political crisis, this second round took place solely so that the government could balance its books before the 2015 federal election. Spending on international assistance at the end of Harper's government was cut well below its average commitment.

This was the situation the Trudeau government inherited. It was not its fault, but is now its responsibility.

By keeping most of the discretionary cuts imposed in the last years of the Harper government, the first Liberal budget actually had a lower commitment to development (0.26% of GNI) than the average of the Harper government (0.30%).

If the Trudeau government remains on its present course, it will have the lowest commitment to international assistance of any Canadian government in the last half-century, significantly below the already low performance of the Jean Chrétien, Paul Martin and Stephen Harper governments ([exhibit 5](#)).

Not surprisingly, Canada's present performance is below all international benchmarks.

- ▶ Canada's commitment to development (0.26 percent of GNI) is half that of its peer group (0.54 percent). In other words, we would need to double our international assistance to do our fair share compared to the G7 and like-minded countries ([exhibit 6](#)).
- ▶ A common reference point is the average country effort of the OECD Development Assistance committee (DAC). The DAC is less relevant than Canada's peer group, as it includes former aid recipients such as the Slovak Republic who are just starting as donors at a very low level. Nevertheless, Canada's performance is well below this less ambitious DAC average country effort (0.41 percent).
- ▶ The cheapest, although arguably least relevant, international benchmark is the weighted average commitment of DAC members. Weighting the average drags the number down further, as the two largest DAC economies—Japan and the US—have very low commitments to development. Canada is below even this lowest of international benchmarks (0.33 percent).³

In conclusion, Canada today is far behind its historical role and international benchmarks ([exhibit 7](#)).

The world applauded when Prime Minister Trudeau said, the day after his election: "To this country's friends around the world.... We're back."⁴ However, when it comes to offering real help, we are not back—we are far back.

4. The Human Cost of Canada's Commitment Gap is equivalent to half a million lives per year

Discussing hundredths of a percentage point of gross national income sounds distant, academic, almost trivial. Yet the human impact is all too real.

A hundredth of a percent of GNI, is the same as 1 cent per \$100 of national income. With Canada's gross national income this year of almost exactly \$2 trillion, 1 cent represents \$200 million. This 1 cent could provide food, shelter and support for 160,000 Syrian refugees in Jordan, or primary schooling for 1 million girls in Africa.⁵

There are many effective uses for development assistance, but perhaps the most fundamental is to save lives. So how many lives could 1 more cent per \$100 of national income save? Using a conservative estimate of \$8000 per death averted, 1 more cent per 100 dollars of national income would save a minimum of 25,000 people every year, mostly women and children.

How did we come to \$8000 per death averted? We assembled four categories of estimates:

1. *Specific health interventions.* Canada has supported a number of highly effective, low-cost interventions such as vitamin A capsules (\$450 per death averted) and insecticide-treated bed nets (\$1600 per death averted).
2. *Global initiatives.* At the 2016 Global Fund replenishment, hosted by Prime Minister Trudeau, the Fund declared the US\$12.9 billion raised would "save over 8 million lives"⁶ (i.e. cost per death averted of US\$1600). GAVI estimates that the latest round of US\$7.5 billion in pledges will lead to "5-6 million premature deaths being averted". Including allocations by implementing countries of US\$1.2 billion, cost per death averted is US\$1450-1740.⁷
3. *Health-system wide improvements.* The incremental cost per child saved in low-income countries from 2000 to 2013 is estimated at US\$4205⁸.

4. *Future-looking scenarios.* Recent studies suggest that 2 million maternal deaths, stillbirths and neonatal deaths could be averted annually by 2020 at a cost per death averted of US\$1928⁹; and low-income countries could have health outcomes similar to those of advanced economies within a generation, at a cost of US\$5700 per death averted.¹⁰

In order to be prudent, we used \$8000 per death averted, which is above all these estimates ([exhibit 7a](#)).

Of course, the total human impact of health interventions goes well beyond lives saved. For example, one more cent on Sexual and Reproductive Rights and Health (SRHR) would save the lives of over 25,000 mothers and newborns each year. At the same time, it would empower 9 million women with control over their own bodies, preventing 2 million unwanted pregnancies and half a million unsafe abortions each year.¹¹ Studies show that giving women control over their bodies increases earnings, health and education outcomes for the entire family.¹² The overall impact, beyond the crucial 25,000 lives saved, would be far-reaching and powerful.

Depending on the development context, there may be other development priorities that are even more impactful than health investments. However, given the critical importance of health, the proven impact of large-scale health interventions, and the underfunded opportunities to do significantly more, we use lives saved through health investments as the common metric to assess the human impact of Canada's commitment gap: i.e. 1 cent of national income equals 25,000 Lives-Saved Equivalents (LSE).

The potential to save tens of thousands and to transform the futures of millions with each additional cent is clear. However, there is a tragic corollary. For each cent that is not spent, the same number of lives are lost. The gap between what Canada is spending and what Canada should be spending can be measured in lives that were not saved.

For a quarter of a century, across Conservative and Liberal governments, Canada committed an average of 0.46 percent of its GNI to international assistance, or 46 cents in every \$100 of national income. Today, we are committing only 26 cents. Using the metric of 25,000 LSEs per cent, the gap of 20 cents is equal to the equivalent of 500,000 lives that were not saved in 2016. (The more detailed analysis used in [exhibit 8](#) refines the estimate to 491,000 lives.) For comparison, the total number of people who have died in the Syrian conflict since March, 2011 is estimated at about 400,000.¹³

The gap between the Trudeau government in its first year (26 cents) and the average of the Harper government (30 cents) is 4 cents, or 100,000 lives-saved-equivalents. In other words, if the government had merely committed the same share of national income as the average of the Harper government, and had focused this spending on proven health interventions, 100,000 additional lives could have been saved in 2016.

Since 1995, the total cost of Canada's failing to meet its historical commitment to development is a staggering 7 million Lives-Saved-Equivalents ([exhibit 8](#)).

The human cost of the Canadian government's financing gap cannot be closed by private sector financing. The private sector has a key role to play in funding infrastructure, creating businesses, supporting economic growth. However, the private sector cannot fund the vaccines and primary health care that could save millions of lives. It cannot support the 60 million refugees and displaced people needing shelter and care. It cannot feed the millions requiring food aid. It cannot pay for large scale basic education in low-income or fragile states. The private sector and private sector financing are complements to—not substitutes for—the critical role played by official development assistance to save lives and build futures in the most challenging places of the world.

The Lives-Saved-Equivalent metric is new, and the results are shocking, so there will naturally be pushback. The metric of \$8000 per death averted is conservative. However, let us assume for argument's sake that the cost per death averted is twice as high (\$16,000). The annual impact of Canada's stepping back from our traditional level of commitment would still be 250,000 lives per year, with a total lives not saved since 1995 of 3.5 million. These are not numbers that we can in good conscience ignore.

In 2015, the tragic death of three-year old Alan Kurdi put a face and a name to the thousands of refugees perishing in the Mediterranean. However, all too often the most vulnerable suffer and die in obscurity. The sad, inescapable reality is that, because of Canada's reduced assistance, people are dying around the world each year even if we do not see them expire. With restored assistance, hundreds of thousands of lives would be saved and millions of futures transformed.

5. The Strategic Investment Case for International Assistance, benefitting Canada and the world

A strategic way to shape a better world

In addition to its crucial direct impact on people's lives, international assistance helps shape a better world. International assistance contributes to a positive system dynamic of economic, political and social development within countries and across regions.

International assistance was conceived with this strategic perspective in mind. The Marshall Plan was an inspired response to the challenge of a Europe verging on economic and political collapse. Secretary of State (and former US Army Chief of Staff) George C. Marshall understood that to avoid war you must invest in peace. He argued that: "the United States should do whatever it is able to do to assist in the return of normal economic health in the world, without which there can be no political stability and assured peace. Our policy is... against hunger, poverty, desperation, and chaos."¹⁴

Similarly, the Colombo Plan of 1950 was designed to encourage socio-economic progress and political stability in South Asia, the region with the most poverty in the world¹⁵. Canada was one of the key architects of the Colombo Plan. In the middle of the Korean War, the Louis St. Laurent government underlined that "equally important" to military force were "constructive endeavours to improve the standards of human welfare in under-developed countries".¹⁶

Of benefit to Canada

International assistance benefits Canada. China has gone from being the second largest recipient of Canadian aid 20 years ago to the second largest market for Canadian products today. Some point to China's success to argue for "trade not aid". In fact, China was for many years the world's largest recipient of international aid. US\$40 billion of international assistance since 1979 laid the foundations for China's present market and trade driven success. Aid begat trade.¹⁷

South Korea was a fragile, war-torn state in the 1950s and a top 5 recipient of aid in the early 1960s. Today it is an advanced economy and has been a net donor for over a decade. It is an important partner and growing market for Canadian products.¹⁸

Infectious diseases are another obvious example of Canadians benefitting from assisting others. Polio infected thousands of Canadian children into the 1950s and still affected over 300,000 children annually around the world until the 1980s. Every Canadian child still needs to be vaccinated against it. It is on the verge of being eliminated. The net present value to Canada and other countries of total elimination is estimated at over \$20 billion.¹⁹ Strengthening health systems around the world helps protect Canadians from infectious diseases at home.

International assistance provides root cause problem-solving and preventative maintenance for the planet. For example, with 65 million displaced people in the world, generous refugee resettlement programmes such as the thousands of Syrian refugees taken in by Canada will never be sufficient. By helping to increase prosperity and reduce conflict in fragile states, international assistance can reduce the number of people taking refuge in the first place. It helps rebuild communities and economies after conflict, allowing refugees and internally displaced people to return to their homes.

Effective international assistance has positive system-wide effects that benefit Canada. It enhances global prosperity, stability and security. It builds 'global public goods' such as human rights, health systems, and peace. It helps reduce 'global public bads' such as crime, terrorism, and infectious diseases.

Lester B. Pearson wrote in 1970: "It becomes more apparent with every passing day that the interests of each nation and each (hu)man are inseparable from those of all others."²⁰ This is even more true today.

The world today at a crossroads

The world today is at a crossroads. Rarely have the two choices been more stark.

One path leads upwards in a virtuous circle. Sustained development results in the effective elimination of extreme poverty by 2030.²¹ Many of today's fragile states in Africa and the Middle East stabilize, with increased prosperity and rule of law. More low-income countries such as Ghana, Bangladesh and Vietnam, graduate to middle income status. Building on the base established with international assistance, private sector driven growth and domestic mobilization of government resources allow these countries to increasingly control their own destinies. Women's and girl's rights are more fully respected. A demographic transition to smaller families and an increased focus on the environment allows more developing countries to address critical issues such as resource (e.g. water, soil, forest) depletion and climate change.

Over time and as a result of sustained progress, there is a reduced need for international assistance and an increased number of players able to share the remaining burden.

There is another path however, a downward spiral. In a time of economic and political uncertainty, development assistance is cut or shifted to humanitarian aid. Fragile states falter and in too many cases fail—increasing human misery and conflict, creating safe-havens for criminality and terrorism, and resulting in new waves of refugees. Refugees and terrorist threats engender nativist reactions in advanced economies. Human rights are degraded in developing and advanced economies as security trumps everything else. The movement of people and goods are restricted, growth falters, and countries look inward. Support for global public goods, such as actions to address climate change, plummets. There is a real danger of global system collapse, and with it the relatively peaceful and prosperous world that we have taken for granted over the last seven decades.

While it is difficult to put a probability on either outcome, the chances of the negative scenario are increasing to a point where we should all be concerned. Canada's values as well as core strategic interests are at stake.

Canada has a significant role to play

Canada has a significant role to play in helping to influence which scenario becomes reality. Perhaps to the greatest extent since the decade after WWII, Canada's actions really matter. We have a charismatic, globally-committed prime minister with a strong majority in parliament who has caught the world's imagination. We have broad public support for Canada making a difference in the world.²² We have the healthiest government balance sheet in the G7.²³ We are uniquely positioned within the G7 to make a significant difference at this critical time, through our own actions and through the influence we have on others.

With increased international assistance and innovative approaches, Canada could influence the future direction of key fragile states such as Mali and Niger in the Sahel region of Africa, Haiti and Afghanistan. Across developing countries, Canada is well positioned to engage constructively on sensitive issues with important development impacts, such as good government, rule of law, and sexual and reproductive rights and health.

Given the global attention on Canada and its upcoming G7 leadership role, Canadian leadership could have a significant influence on the actions of others. We saw this very concretely during Canada's successful leadership of The Global Fund replenishment in September 2016.

To recap, international assistance plays a strategic role that helps create the conditions for prosperity and security. Canada has benefited greatly from this. At a time when the world is at a crossroads, Canada has a particularly important role to play. What a pity, and potentially tragedy, therefore that Canada has been taking such a minimalist approach to international assistance.



6. This is our time

The strategic and human arguments are clear. Canada's stepping up at this critical time could contribute to a more stable and prosperous world while saving hundreds of thousands of lives. So what does it take to make it happen?

Support for international assistance is not a partisan issue. It is a generational and, above all, a leadership issue. For two generations after WWII, leaders on both sides of the house, remembering what happened when international obligations were neglected, supported Canada's playing a strong role in international assistance. Over the last 20 years, a generation of leaders on both sides of the house stepped back from Canada's international role and let other countries do the heavy lifting.

Many have expressed concern at U.S. President-elect Donald Trump's rhetoric around "America First" and his possibly stepping back from NATO commitments and nation building abroad. In fact, Canada has been the one quietly playing a "Canada first" approach to international burden-sharing for the last two decades, shirking its fair share.

That time is gone. Other countries are tapped out. The world is looking to Canada to step-up again. It is in our own strategic self-interest, as well as in accordance with our deepest values, to do so.

A whole of cabinet decision

However, closing Canada's commitment gap cannot depend on the Minister of International Development convincing the Minister of Finance of aid's short-term Return On Investment (ROI) for Canada. Short-term ROI is not the right metric for international assistance. International Development ministers are not the only members of cabinet that should be making the strategic case for international assistance.

Countries step up on international assistance when heads of government and/or senior cabinet ministers (especially foreign affairs, defence and finance) champion

the strategic imperative of investing in a more stable, prosperous world and reach-out across the aisle to build long-term, cross-partisan support.

Canada endorsed the Colombo Plan because Defence Minister Brooke Claxton actively supported Secretary of State for External Affairs Lester B. Pearson in making the case to an initially sceptical cabinet. They jointly approved the memo endorsing Canadian support. Claxton argued to cabinet that the strategic aspect of the Colombo Plan was "real and considerable". It moved forward when prime minister Louis St. Laurent threw his weight behind it. The Conservatives supported the investment and on the Colombo Plan's 10th anniversary, prime minister Diefenbaker applauded "the realization that the economic progress of all parts of the world is an essential element of any satisfying and enduring peace".²⁴

The Marshall Plan succeeded, despite considerable initial misgivings in the Republican-controlled Senate, thanks to the strong support of President Truman and Republican isolationist-turned-internationalist Senator Vandenberg.

Starting with the Prime Minister himself, the Trudeau cabinet is one of the most globally engaged in history. In addition to a Minister of Foreign Affairs with an activist policy agenda, a Minister of International Development with a deep personal understanding of development, and an International Trade Minister who is a leading expert on global issues, the cabinet includes a:

- ▶ Defence minister who served in Afghanistan,
- ▶ Health minister who spent 10 years in Niger
- ▶ Finance minister who supported schools in Africa
- ▶ Environment and Climate Change minister who lived in East Timor
- ▶ President of the Treasury Board who negotiated human rights agreements with Colombia

Champions from this group will be critical to making the case that international assistance is in Canada's strategic best interest.

The UK example

Canada's situation today is similar to the UK in 1997 when Tony Blair's Labour government was first elected. UK's international assistance in 1997 was the same as Canada's today: 0.26 percent of GNI ([exhibit 9](#)). The economic situation was challenging and the new government had a very ambitious domestic agenda.

Thanks to the strong leadership of prime minister Tony Blair and chancellor Gordon Brown, which was continued by Conservative prime minister Cameron, the UK transformed its international assistance performance. UK's development agency became the most effective and respected on the planet. In 2013, after 16 years of sustained effort, the UK became the first G7 country to reach 0.7 percent. In recognition of the UK's development leadership, prime minister Cameron was asked to co-chair the UN high-level panel that crafted what became the Sustainable Development Goals (SDGs)—setting the global agenda for the next 15 years. In 2015, with strong cross-party support, the UK enshrined its 0.7 percent commitment into law.²⁵ UK's international assistance has had a significant global impact, shaping a better world.

If the UK, starting from the same base, could accomplish this, why not Canada?

Cross-partisan and public support for Canada to step up

There is cross-partisan and public support for government action. Engineers Without Borders has found that: 94% of Canadians believe it is important to improve health, education, and economic opportunity for the world's poorest people; 62% agree that Canada should be one of the leading countries in providing international assistance²⁶.

The Standing Committee of Finance recently recommended that Canada "increase its investments in official development assistance with the goal of investing

0.35 percent of gross domestic product in the next three to four years."²⁷ The Standing Committee on Foreign Affairs and International Development recommended "Canada spending 0.7 percent of gross national income (GNI) on official development assistance (ODA) by 2030. The first stage of that plan should see the government increase spending to 0.35 percent of GNI on ODA in 2020."²⁸

The Trudeau government has inspired Canadians with the notion that "better is always possible". They have taken real action to give life to this notion on climate change, on child tax credits, on reconciliation with indigenous peoples, on infrastructure. It is now time to show that "better is always possible" with international assistance.

Although the discussion of getting to 0.7% is a legitimate longer-term goal, Canada is very far from that right now. For the 2017 budget that will be "informed" by the International Assistance Review the issues are:

- ▶ Not about getting to 0.7 percent, but about getting back to at least half of 0.7 percent
- ▶ Not about the Trudeau government being the best for international assistance, but about changing course from being the worst
- ▶ Not yet about being a development leader, but about doing our fair share.


Despite being a key tool for shaping a better world, international assistance is a mere 2 percent of the Federal budget. Fiscally, significant improvements in international assistance are possible. In budget 2017, as in every budget, tough decisions will have to be made, red lines will have to be drawn. However, this time, the red line should not be drawn across the backs of the poorest and most vulnerable of the planet.

Budget 2017 can be the moment when the Trudeau government puts Canada, after two decades of free-riding, back on a path to being a fully paid-up member of the international community.

- [1] Trudeau, Justin. Prime Minister. (2016). Address to the United Nations General Assembly, September 20, 2016.
- [2] Department for International Development, United Kingdom. (2015). [Policy Paper: Official Development Assistance](#).
- [3] All OECD DAC figures from, or calculated from OECD DAC1: [Total flows by donor](#).
- [4] Trudeau, Justin. Prime Minister Designate. (2015). Remarks at Ottawa Rally, October 20, 2015.
- [5] Figures from UNESCO. (2015). [Pricing the Right to Education: The cost of reaching new targets by 2030](#). Education for All Global Monitoring Report – Policy Paper 18; and IFRC. (2015). [Emergency Items Catalogue](#).
- [6] The Global Fund. (2016). [Global Fund Donors Pledge Nearly \\$13 Billion to Help End Epidemics](#), 17 September 2016.
- [7] Gavi, the Vaccine Alliance. (2015). [World Leaders Make Record-breaking commitment to protect poorest children with vaccines](#), 27 January, 2015.
- [8] Murray, C., et al. (2015). [Keeping score: fostering accountability for children's lives](#). The Lancet, 386 (9988):3-5.
- [9] Bhutta, Z.A., et al. (2014) [Can available interventions end preventable deaths in mothers, newborn babies, and stillbirths, and at what cost?](#) The Lancet, 384 (9940):347-370.
- [10] Jamison, D.T., et al. (2013). [Global Health 2035: a world converging within a generation](#). The Lancet, 382 (9908):1898-1955.
- [11] Figures calculated based on Singh, S., Darroch, J.E., and Ashford, L.S. (2014). [Adding It Up: The Costs and Benefits of Investing in Sexual and Reproductive Health 2014](#). Guttmacher Institute; and FP2020 (2016) resources.
- [12] Bailey, M.J. (2013). [Fifty Years of Family Planning: New Evidence on the Long-Run Effects of Increasing Access to Contraception](#). Brookings Papers on Economic Activity, 2013, 341-409.
- [13] de Mistura, S. UN Special Envoy for Syria. (2016). Remarks, April 22. Geneva.
- [14] Marshall, George, C. (1947). The “Marshall Plan” speech at Harvard University, June 5, 1947.
- [15] The Commonwealth Consultative Committee. (1950). [The Colombo Plan for Co-operative Economic Development in South and South-East Asia](#). Report by the Commonwealth Consultative Committee, London, September and October 1950.
- [16] Canada. (1951, January 30). Speech from The Throne, to open the 4th session of Parliament of the 21st Parliament of Canada. Ottawa. Government of Canada.
- [17] Figures from OECD DAC 2a, [Aid \(ODA\) disbursements to countries and regions](#); and Statistics Canada. (2016). Summary Tables. [Imports, exports and trade balance of goods on a balance-of-payments basis, by country or country grouping](#).
- [18] Figures from OECD DAC 2a, [Aid \(ODA\) disbursements to countries and regions](#); and Statistics Canada. (2016). Summary Tables. [Imports, exports and trade balance of goods on a balance-of-payments basis, by country or country grouping](#). See: Marx, A., and Soares, J. (2013). [South Korea's Transition from Recipient to DAC Donor: Assessing Korea's Development Cooperation Policy](#). International Development Policy, Graduate Institute of International and Development Studies.
- [19] “If the virus [polio] is eradicated in 2019, as projected, an additional US \$20-25 billion will be saved, in health costs and productivity losses by 2035.” Global Polio Eradication Initiative. (2016). [Investment Case](#). April 2016.
- [20] Pearson, Lester, B. (1970). [The Pearson Report: A New Strategy for Global Development](#). The UNESCO Courier.
- [21] United Nations. (2013). [A New Global Partnership: Eradicate poverty and transform economies through sustainable development](#). Report of the High Level Panel of Eminent Persons on the Post-2015 Development Agenda. United Nations Publications. New York, NY.
- [22] Canadians poll favourably supporting international development. Engineers Without Borders Canada. (2015). [Raw Data from Canadian Perspectives on International Development](#).
- [23] Since 2005, Canada has held the lowest debt-to-GDP ratio among G7 countries. International Monetary Fund. (2016). [World Economic Outlook Database](#), October 2016.
- [24] Diefenbaker, John, G. Prime Minister. (1960). Preface to a booklet commemorating the tenth anniversary of the foundation of the Colombo Plan.
- [25] United Kingdom Parliament. (2016). [The 0.7 Aid Target](#). House of Commons Library. Commons Briefing Paper SN03714.
- [26] Engineers Without Borders Canada. (2015). [Raw Data from Canadian Perspectives on International Development](#).
- [27] Canada, Parliament, House of Commons. Standing Committee on Finance. (2016). [Report of the Standing Committee on Finance: Creating the Conditions for Economic Growth: Tools for People, Businesses and Communities](#). 42nd Parl. 1st Sess.
- [28] Canada, Parliament, House of Commons. Standing Committee on Foreign Affairs and International Development. (2016) [Report of the Standing Committee on Foreign Affairs and International Development: Development Cooperation for a More Stable, Inclusive and Prosperous World: A Collective Ambition](#). 42nd Parl. 1st Sess.

Exhibit 1

Canada is in last place with Japan amongst global peers.



*Switzerland defense spending from SIPRI was multiplied by 1.18 to account for military expenditure at the Canton level and military pensions – included in other countries' military expenditure

Source: ODA spending as a percentage of GDP calculated from OECD DAC 1 ODA Statistics: Fund flows: Net disbursements, Amount type: Current prices; and, OECD National Accounts 1. Gross Domestic Product B1_GE (expenditure approach), Current Prices, Current Exchange Rates, Unit: US dollar, million. Defense spending as a percentage of GDP calculated from SIPRI "Military expenditure by country as a percentage of gross domestic product, 1988-2015".00

Exhibit 2

Canada fails to reach halfway to international benchmark in either development or defence

		Japan	Canada	Switzerland*	Italy	Germany	Netherlands	Australia	France	Sweden	Norway	UK*	USA
Development	ODA as Percent of GNI	0.22%	0.28%	0.52%	0.21%	0.52%	0.76%	0.27%	0.37%	1.40%	1.05%	0.71%	0.17
	Percent of UN ODA Target (0.7% GNI)	31%	40%	75%	30%	74%	109%	38%	53%	201%	149%	102%	25%
Defense	Defense Expenditure as Percent of GDP	0.99%	0.97%	0.84%	1.31%	1.18%	1.16%	1.92%	2.10%	1.11%	1.50%	1.96%	3.32%
	Percent of NATO Target (2.0% GDP)	49%	48%	42%	66%	59%	58%	96%	105%	55%	75%	98%	166%


Legend: Countries that contribute 2% or more of GDP towards military expenditure, the NATO target, the cell is green. Countries that contribute 1% - half the target – or more of GDP to military expenditure, the cell is yellow. Countries that contribute less than 1% of GDP towards military expenditure, the cell is red. Countries that contribute 0.7% (The Pearson ODA Target) or more of GNI towards ODA, the cell is green. Countries that contribute 0.35% of GNI or more - half of the ODA target, the cell is yellow. Countries that contribute less than 0.35% of GNI, the cell is red.

*Switzerland defense spending from SIPRI was multiplied by 1.18 to account for military expenditure at the Canton level and military pensions – included in other countries' military expenditure; UK defense spending counted as having reached the 2.0 target as UK policy stipulates annual military spending of 2.0% of GDP

Source: ODA spending as a percentage of GNI calculated from OECD DAC 1 ODA Statistics. Fund flows: Net disbursements, Amount type: Current prices, Unit: US dollar, million; and OECD Gross National Income: Measure: Current prices, Unit: US dollar, million. Defense spending as a percentage of GDP calculated from SIPRI "Military expenditure by country as a percentage of gross domestic product, 1988-2015".

Exhibit 3

Canada support for international assistance near all-time low




Note: Dashed line represents 2016 ODA/GNI estimate; years are determined based on the political party which was in government for the majority of the year.

Source: ODA spending as a percentage of GNI from OECD DAC 1 ODA Statistics. Fund flows: net disbursements. Amount type: current prices, US Dollar, millions; 2016 estimate based on 2015-16 Report to Parliament on Official Development Assistance and CCIC Update on Canadian Official Development Assistance, October 2016.

Exhibit 4

Cuts to development assistance three times deep as cuts to domestic programs




Note: Program spending as % of GDP cut from 15.7% in 1990/91 to 13.7% in 2015/16. ODA as % of GNI cut from 0.44% in 1990 to an estimated 0.26% in 2016

Source: ODA spending calculated from OECD DAC 1 ODA Statistics. Data current as of October 4, 2016; Estimates for 2016 ODA expenditure based on an estimated ODA/GNI of 0.26. estimate based on, 2015-16 Report to Parliament on Official Development Assistance and CCIC Update on Canadian Official Development Assistance, October 2016.

Exhibit 5

On Present Path Trudeau Government Will Show Lowest Commitment to Development in Fifty years




*Trudeau includes PM Turner (1984)

** Mulroney includes PM Campbell (1993)

Source: ODA spending as a percentage of GNI from OECD DAC 1 ODA Statistics. Fund flows: net disbursements. Amount type: current prices, US Dollar, millions; weight of each Prime Minister's tenure calculated based on Prime Ministers of Canada Biographical Information from Parliament of Canada, based on date sworn in; Situation Today estimate based on 2015-16 Report to Parliament on Official Development Assistance and CCIC Update on Canadian Official Development Assistance, October 2016.

Exhibit 6

Canada's commitment to development half its peer group average




Source: ODA spending calculated from OECD DAC 1 ODA Statistics: Fund flows: Net disbursements, Amount type: Current prices, Unit: US Dollars, millions. Data current as of October 4, 2016.

Note: Canada 0.28% is based on OECD 2015 data. Estimates for 2016 is a further reduction to 0.26%

“To Canada’s friends all around the world...we’re back!”*

Exhibit 7 Canada today is far back Compared to its international peer group and own historical performance




Sources: OECD DAC. All figures refer to 2015 (latest year for data) unless otherwise indicated. Canada today based on 2015-16 Report to Parliament on Official Development Assistance and CCIC Update on Canadian Official Development Assistance, October 2016. Data current as of October 2016.

*Justin Trudeau, October 20, 2015

**G7 Plus mid-sized open economies (Australia, Norway, Netherlands, Sweden, Switzerland)

Exhibit 7A

Developing a reasonable cost per death averted




Source: [Caulfield, 2006](#); [Robbertstad, 2004](#); [UNICEF, 2005](#); [Dye, 2006](#); [Willey, 2012](#); [The Global Fund, 2016A](#); [The Global Fund, 2016B](#); [Gavi, 2015](#); [Murray, 2015](#); [Bhutta, 2014](#); and [Jamison, 2013](#).

Exhibit 8

Human Cost of Canada's Commitment Gap

Lives (Not) Saved Equivalents by year 1996-2016

Total: 7,250,000




*2016 estimate based on 2015-16 Report to Parliament on Official Development Assistance and CCIC Update on Canadian Official Development Assistance, October 2016.

Source: Prices adjustments calculated with Bank of Canada Inflation Calculator, 2002 CPI = 100.

Source: ODA spending as a percentage of GNI from OECD DAC 1 ODA Statistics. Fund flows: net disbursements. Amount type: national currency, millions; Cost per death averted estimated as \$8000 2016 Canadian dollars, values adjusted for earlier years based on Bank of Canada's CPI Calculator.

Exhibit 9

Potential to Lead: Canada today in same place as UK in 1997



Source: Official Development Assistance as percent of Gross National Income. Calculated from OECD DAC 1 ODA Statistics. Fund flows: Net disbursements. Amount type: Current prices.

*2016 Canadian Estimate from Report to Parliament on Official Development Assistance and CCIC Update on Canadian Official Development Assistance, October 2016. 2016 UK estimate based on UK annual commitment to 0.7% ODA/GNI.